

Engineering Estimate of civil work 1st floor office Building

Sr #	M.R.S	Descriptions	Unit	Qty	Rate	Amount
1	Ch-25,Item 57	Providing and fixing aluminium glazed partition of anodized bronze colour using section of M/s. Al-Cop/ Pakistan Cable having 2 mm thick Frame size D48-A , i/c 12 mm tinted TEMPERED glass with sand blasting and edge polishing i/c the cost of tear resistance film,rubber gasket and hardware etc. complete in all respect as approved and directed by the Engineer Incharge.	SFT	448		
2	Ch-25,Item 57	fixing aluminium glazed partition of anodized bronze colour using section of M/s. Al-Cop/ Pakistan Cable having 2 mm thick Frame size D48-A , i/c 12 mm tinted TEMPERED glass with sand blasting and edge polishing i/c the cost of tear resistance film,rubber gasket and hardware etc. complete in all respect as approved and directed by the Engineer Incharge.(Labour only)	SFT	256		
3	Ch-9,Item 48	Providing and fixing false ceiling comprises of Gypsum board laminated sheet of size 2'x2'/2'x3'/ 3'x3'of specified design and thickness i/c cost of fixtures i.e galvanized angle 1" x 1" at wall sides, galvanized tee 1¼" x 1"and 1 ½" x 1" both at 4' c/c (made of Taiwan CKM or equivalent), hanging with G.I/Copper wire 16 SWG, G.I hook, Rawal Plug etc:9 mm thick complete in all respects as approved and directed by the Engineer Incharge.	SFT	90		
4	Ch-4,Item 13	Dismantling brick work in cement mortar	CFT	32		
5	Ch,12 Item 68	Providing and fixing heavy duty 3 mm thick SS Plate, die-cast metal Providing and fixing heavy duty 3 mm thick SS Plate, die-cast metal embeded in floor i/c the cost of Top pivot hinge,hardware, cutting of floor and making it good complete in all respect as approved and directed by the Engineer Incharge	Each	1		
6	Ch,25 Item 64	providing and fixing 2'-9" high stair railing comprising of non magnetic (304) Stain less steel 2" dia pipe railing of 18 SWG welded with vertical posts of 2" dia stainless steel round/ Squar pipe @ 2-ft c/c fixed on alternate steps with 3" long steel screws and brass rawal plugs , 3-Nos diagonal stainless steel pipes of 1/2" dia passes through goties fixed on vertical post, i/c stainles steel welding, fixing & polishing complete in all respects as approved and directed by the Engineer Incharge.	SFT	154		
7	Ch.13 item 31+32	Preparing surface and painting with emulsion paint:- (3coat) ceilling	SFT	500		

Sub total

5%PRA

Grand Total